


# 150.1165 | Floor Mounted Tub Filler With Hand Held Shower





## SPECIFICATIONS:

- Solid Brass construction includes valve
- Floor Mount Installation
- Hand shower flow rate = 2.0 GPM @ 60 PSI w/ back flow prevention
- Diverter knob controls water flow between spout and hand held
- 7.0 GPM Spout flow rate
- With 360° Swivel Spout

#### FINISHES:

• Chrome - 150.1165CP

## **STANDARDS:**

• ASME A112.18.1 / CSA B125.1

Legislation Compliance







# **Technical Diagram**

