


# 260.1165 | Floor Mounted Tub Filler With Hand Held Shower





### SPECIFICATIONS:

- Solid Brass construction includes valve
- Floor Mount Installation
- Hand Shower Flow Rate = 2.0 GPM @ 60 PSI w/ back flow prevention
- Diverter knob controls water flow between spout and hand held
- 8.0 GPM Spout Flow Rate.

## FINISHES:

• Chrome - 260.1165CP, Brushed Nickel - 260.1165BN

### **STANDARDS:**

• ASME A112.18.1 / CSA B125.1

Legislation Compliance







1/2" NPT

# **Technical Diagram**

